Step 1: Driving Circuit Leak Test		
Setup:  a) Connect the inspiratory and expiratory limbs of the Cerebrus system to the corresponding inspiratory and expiratory ports of the driving ventilator  b) Occlude the patient Y of each secondary circuit	Performance:  I. Perform a standard low P leak test using an anesthetic gas machine	PASS  ● Leak < 500 mL
Step 2: Secondary Circuit Leak Te	st	
Setup: a) Connect test lungs to the end of each secondary circuit* b) Set driving ventilator to initial system setup up parameters c) Begin ventilation on test lungs  * Anesthetic gas machine (AGM) breathing bags can be used as test lungs*	Performance I. Allow the test lungs inflate and deflate II. Allow 2 minutes of ventilation III. Note the total volume returned to the ventilator IV. Allow the lungs to ventilate for an additional 2 minutes	<ul> <li>Each test lung visually inflates and deflates with each respiratory cycle of the driving ventilator</li> <li>Volume return to the ventilator remains constant for 2 minutes after the total volume was noted</li> </ul>
Step 3: Fresh Gas Flow Check  Setup:  a) Ensure the fresh gas flows to each secondary circuit is attached  b) Set each fresh gas flow to 4 L/min	Performance I. With each fresh gas flow set to 4 L/min allow 2 minutes of ventilation II. After 2 minutes note the total volume returned to the ventilator III. Change the fresh gas flow on Lung A to 15 L/min while holding lung B at 4 L/min	PASS (all conditions must be met)  • breath-delivery bag inflates and deflates with each respiratory cycle of the driving ventilator  • Increased volume returned to driving ventilator AND increased lung expansion of Lung A following Step VI

	<ul> <li>IV. Ventilate for 2 minutes</li> <li>V. Note the total volume returned to the ventilator</li> <li>VI. Note any change in the observed inflation in Lung A</li> <li>VII. Return fresh gas flow on Lung A to 4 L/min</li> <li>VIII. Repeat steps (III – VII) with lung B set to 15 I/min and lung A held at 4 L/min</li> </ul>	Increased volume returned to driving ventilator AND increased lung inflation of Lung B following Step VIII
Step 4: Secondary Circuit Independ	ence	
Setup:  a) Set driving ventilator to initial system setup up parameters  b) Set fresh gas flow to 4 L/min  c) Begin ventilation on test lungs	Performance:  I. Allow system to ventilate for 2 minutes  II. Measure the tidal volume or visually observe the approximate inflation of each lung  III. Decrease the compliance in Lung A  IV. Ventilate for 1 min  V. Measure the tidal volume lung B or visually observe the approximate inflation of Lung B  VI. Return the compliance of Lung A to baseline  VII. Repeat steps (III – VI) using Lung B	No major changes in measured tidal volume or observed inflation of lung B when lung A compliance is decreased      AND      No major changes in measured tidal volumes or observed inflation of lung A when lung B compliance is decreased
Step 5: Manometer Check		
Setup: a) Set driving ventilator to initial system setup parameters b) Ensure manometer is installed into the sampling port of the HME filter distal to the patient Y	Performance:  I. Note the nadir (lowest reading) on the manometer  II. Note the zenith (highest reading) on the manometer  Please refer to the instructions on how to read the manometer	<ul> <li>PASS</li> <li>Nadir occurs at end expiration (PEEP) and the manometer reads at least 5 cm H<sub>2</sub>O*</li> <li>PEEP may be higher than 5 cm H<sub>2</sub>O due to intrinsic PEEP generated by the constant fresh gas flow. Higher fresh gas flow rates lead to higher intrinsic PEEP</li> </ul>

c) d) e)	Ensure each secondary circuit is attached to a test lung Ensure the PEEP valves on each secondary expiratory limb is set to 5 cm H <sub>2</sub> O Set fresh gas flow rates for each secondary circuit is set to 4 L/min			•	Zenith (peak inspiratory pressure) occurs with each inspiration  O Peak inspiratory pressure does not equal the driving pressure of the ventilator			
Step 6: Disconnect Alarm								
Seti	ıp:	Perfo	rmance:	PAS	S			
a)	Set driving ventilator to initial system setup up parameters Set fresh gas flow to 4 L/min for each secondary circuit Begin ventilation on test lungs	II. III. IV. V.	Allow lungs to ventilate for 2 minutes to reach steady state Set volume alarms according to instructions on ALARM SETTING Disconnect Lung A Reconnect Lung B Reconnect Lung B	•	Disconnect of Lung A results in low volume alarm  AND  Disconnect of Lung B results in low volume alarm			
Ster	7: Pop-Off Valve Integrity AND	Occlu	sion Alarm					
	Set driving ventilator to		ormance:	PAS	S			
,	initial system setup up	l.	Allow lungs to ventilate for 2 minutes to	•	Clamping of Lung A results in:			
	parameters		reach steady state	•	Low volume alarm			
b)	Set fresh gas flow to 8 L/min	II.	Set volume alarms according to	•	Peak inspiratory pressure as measured by inline			
	for each secondary circuit		instructions on "Alarm Settings"		manometer = 45 cm H <sub>2</sub> O			
c)	Begin ventilation on test	III.	Clamp Lung A distal to secondary circuit Y					
	lungs	IV.	Note peak pressure on Lung A as		AND			
		١.,	measured by inline manometer					
		V.	Unclamp Lung A	•	Clamping of Lung B results in:			
		VI.	Allow lungs to ventilate until volume alarm ceases	•	Low volume alarm			
		VII.	Clamp Lung B distal to secondary circuit Y	•	Peak inspiratory pressure as measured by inline manometer = 45 cm H₂O			

	<ul> <li>YIII. Note peak pressure on Lung B as measured by inline manometer</li> <li>IX. Unclamp Lung A</li> <li>X. Allow lungs to ventilate until volume alarm ceases</li> </ul>	
Step 7: Clamps		
	Performance: I. Locate clamp at each patient bedside	Pass:  • 1 clamp at each patient bedside is easily identified and located